



## Bid Notice Abstract

### Invitation to Bid (ITB)

**Reference Number** 6515412  
**Procuring Entity** PILI WATER DISTRICT  
**Title** Construction of Multi-Purpose Shed and Motorcycle Parking Area  
**Area of Delivery**

<b>Solicitation Number:</b> 19-09-362	<b>Status</b>	<b>Pending</b>
<b>Trade Agreement:</b> Implementing Rules and Regulations	<b>Associated Components</b>	1
<b>Procurement Mode:</b> Public Bidding	<b>Bid Supplements</b>	0
<b>Classification:</b> Civil Works	<b>Document Request List</b>	0
<b>Category:</b> Construction Projects	<b>Date Published</b>	03/10/2019
<b>Approved Budget for the Contract:</b> PHP 1,699,372.60	<b>Last Updated / Time</b>	02/10/2019 14:16 PM
<b>Delivery Period:</b> 45 Day/s	<b>Closing Date / Time</b>	10/10/2019 17:00 PM
<b>Client Agency:</b>		
<b>Contact Person:</b> Rowena Agrito Mongoso BAC-Secretary Sta. Rita Agro-Industrial Estate San Jose Pili Camarines Sur Philippines 4418 63-054-4777136 63-054-4777136 piliwd@yahoo.com		

#### Description

##### INVITATION TO BID

The PILI WATER DISTRICT, through its BIDS AND AWARDS COMMITTEE invites suppliers/manufacturers to apply for eligibility and to bid for the following projects:

Name of Project : Construction of Multi-Purpose Shed and Motorcycle Parking Area  
 Approved Budget of the Contract : (Php)1,699,372.60  
 Cost of Bid Documents : (Php) 5,000.00  
 Contract Duration (CD) 45

The Funding Source is the GOP through the Corporate Budget for 2019 approved by the board. Bids received in excess of the ABC shall be automatically rejected at bid opening. Prospective Bidders should have completed within Five (5) years from the date of submission and receipt of bids, a contract similar to the project and the contract amount should be at least fifty percent (50%) of the ABC to be bid.

Bidding will be conducted through open competitive bidding procedures using non-discretionary pass/fail criterion as specified in the Implementing Rules and Regulations (IRR) of Republic Act 9184 (RA 9184) as amended, otherwise known as the "Government Procurement Reform Act".

The schedule of activities is listed as follows:

##### SCHEDULE OF ACTIVITIES

Construction of Multi-Purpose and Motorcycle Parking Area  
 1. Issuance and Availability of Bidding Documents

- October 3, 2019 to October 22, 2019 (8:00 AM-5:00 PM, Monday-Friday)
- 2. Pre-bid Conference/Site Inspection October 9, 2019 (8:30 AM)
- 3. Deadline of submission and receipt of Bids October 22, 2019 (8:00 AM)
- 4. Opening of Bids October 22, 2019 (8:30 AM)

Bidding Documents may be acquired by interested Bidders from Pili Water District office upon payment of a non-refundable amount stated above and can be viewed and downloaded at [piliwaterdistrict.com](http://piliwaterdistrict.com)

Bidding is restricted to eligible bidders as described in ITB 5.1.

Bids must be delivered on or before the above stated scheduled dates at Pili Water District office. All bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in ITB Clause 18.1.

The PILI WATER DISTRICT reserves the right to accept or reject any bid, to annul the bidding process, and to reject all bids at any time prior to contract award, without thereby incurring any liability to the affected bidder or bidders.

For further information, please contact:

(Sgd.) ROWENA A. MONGOSO  
BAC Secretary

#### ITEMS OF WORK QTY UNIT

- 1 Safety and Health Kit and PPE 1 lot
- 2 Lay-out and Structure Excavation (Common Soil) 11.37 cu.m.
- 3 Formworks and Scaffoldings 1 lot
- 4 Reinforced Concrete 3.75 cu.m.
- 5 Masonry Works 60.20 sq.m.
- 6 Metal/Steel Works (Cyclone Wire Partition & Gate) 130 sq.m.
- 7 Installation of 3" G.I. Post 29 set
- 8 Fabrication and Installation of Trusses and Purlins 1 lot
- 9 Installation of Roofing, Flushing and Gutter 308 lin.m.
- 10 Concrete Flooring 327 sq.m.
- 11 Electrical Works 1 lot
- 12 Painting Works 1 lot
- 13 Site Clean-up 1 lot
- 14 Information Billboard 1 lot

#### CONSTRUCTION OF MULTI-PURPOSE SHED AND MOTORCYCLE PARKING AREA

- 1. SAFETY AND HEALTH KIT AND PPE
  - A. Safety Kit and PPE 1 lot
- 2. LAYOUT AND STRUCTURE EXCAVATION (COMMON SOIL)
  - Quantity: 11.37 cu.m
- 3. FORMWORKS (1 lot)
  - A. MATERIALS
    - ¼" Marine Plywood 5 pcs
    - 2" x 2" x 12' Coco Lumber 20 pcs
    - 2" x 3" x 12' Coco Lumber 20 pcs
    - CWN, 4" long 3 kgs
    - CWN, 3" long 3 kgs
    - CWN, 2" long 1 kgs
    - CWN, 1½" long 1 kgs
- 4. REINFORCED CONCRETE (3.75 cu.m)
  - A. MATERIALS
    - Portland Cement 30 bags
    - Albay Sand 2 cu.m.
    - ¾" Crushed Gravel 4 cu.m.
    - 12mmØ x 6m RSB 65 pcs
    - 10mmØ x 6m RSB 60 pcs
    - #16 G.I. Tie Wire 5 kgs
- 5. MASONRY WORKS (60.2 sq.m)
  - A. MATERIALS
    - Portland Cement 120 bags
    - Albay Sand 9 cu.m.
    - 5" CHB 760 pcs
    - 10mmØ x 6m RSB 90 pcs
    - #16 G.I. Tie Wire 5 kgs
- 6. METAL/STEEL WORKS (CYCLONE WIRE PARTITION & GATE) (130 SQ. M)
  - A. MATERIALS
    - 1½" Ø Galvanized Iron Pipe S40 74 pcs
    - 10mmØ Plain Round Bar 74 pcs
    - Cyclone Wire 1.5m x 7.5m x 50mm Slot 9 rolls
    - Welding Rod 6013 (2.5mm) 40 kgs
    - Cutting Disc 4" Ø 50 pcs
    - Grinding Disc 4" Ø 20 pcs
    - Hacksaw Blade (Sandflex) 20 pcs
    - 1" Cylindrical Hinges 72 pcs
- 7. INSTALLATION OF 3" G.I. POST (29 SETS)

- A. MATERIALS
- G.I. Pipe 3" Ø S40 17 pcs
- Welding Rod 6013 (2.5mm) 15 kg
- Base Plate 8"x 8"x 3/4" (w/ 4 Holes) 29 pcs
- Cutting Disc 4"Ø 30 pcs
- Grinding Disc 4"Ø 10 pcs
- Machine Bolts, w/washer & nuts 8"x3/4" 116 pcs
- 8. FABRICATION AND INSTALLATION OF TRUSSES and PURLINS (1 LOT)
- A. MATERIALS
- Angle Bar 1 1/2"x 1 1/2"x 1/4" 128 pcs
- Angle Bar 1"x 1"x 1/4" 128 pcs
- Welding Rod 6013 (2.5mm) 30 kg
- C-Purlins 2"x 4"x 1.5mm 115 pcs
- Grinding Disc 4"Ø 20 pcs
- Cutting Disc 4"Ø 40 pcs
- 9. INSTALLATION OF ROOFINGS, FLUSHING AND GUTTER (308 LM)
- A. MATERIALS
- Long Span Dura Rib Type 8.5 m length 28 pc
- Long Span Dura Rib Type 5.8 m length 12 pc
- Spanish Gutter 8" long 17 pc
- Wall Flushing 8" long 13 pc
- Blind Rivets 2 box
- Teksrew 2" 1500 pc
- 10. CONCRETE FLOORING (327 SQ.M)
- A. MATERIALS
- Cement 250 bags
- Albay Sand 18 cu.m
- Crushed Gravel 3/4" 34 cu.m
- Reinforcing Steel Bars 9mmØ 130 pcs
- #16 G.I. Tie Wire 4 kg
- 11. ELECTRICAL WORKS (1 LOT)
- A. MATERIALS
- Corrugated PVC Electrical Conduit, 1/2" 75 m
- CFL 20w, E27 16 pcs
- Ceiling Receptacle, E27, 4" dia. 16 pcs
- 1-way Switch 2-gang, Flush Type in Plate 2 set
- 1-way Switch 3-gang, Flush Type in Plate 2 set
- Universal Convenience Outlet, 3-gang, 3 set
- Junction Box with Cover 4 pcs
- Utility Box 7 pcs
- Pull Box 4 x 8 x 8 1 pcs
- Stranded Copper Wire, 5.5 mm<sup>2</sup>, THHN 1 box
- Stranded Copper Wire, 3.5 mm<sup>2</sup>, THHN 1 box
- Stranded Copper Wire, 2.0 mm<sup>2</sup>, THHN 2 box
- Cable Tie 10" long 100 pcs
- Electrical Tape 5 pcs
- 12 PAINTING WORKS
- A. MATERIALS
- Quick Dry Enamel Paint (Azure Blue) 7 gal
- Epoxy Primer Paint - Gray 10 gal
- Lacquer Thinner 4 gal
- Paint Thinner 4 gal
- Roller Brush 4" long with handle 10 pc
- Paint Brush 2" 10 pc
- Paint Brush 3" 5 pc
- 13. SITE CLEAN-UP ( 1 Lot)
- 14. INFORMATION BILLBOARD (1 lot)
- A. MATERIALS
- Tarp Printing 8ft x 8ft 1 pc
- Marine Plywood 1/4: thk 2 pc
- Cocolumber 2"x 3"x 12' 6 pc
- Cocolumber 2"x 2"x 12' 6 pc
- Common Wire Nail 1 1/2" 2 kg
- Common Wire Nail 4" 2 kg

**Pre-bid Conference**

Date	Time	Venue
09/10/2019	8:30:00 AM	Pili Water District Conference Room Sta. Rita Agro Industrial Estate, San Jose, Pili, Camarines Sur

**Date Created** 02/10/2019

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.

© 2004-2019 DBM Procurement Service. All rights reserved.

[Help](#) | [Contact Us](#) | [Sitemap](#)